

SPECIFICATIONS - DETAILED PROVISIONS
Section 02050 - Demolition and Salvage

C O N T E N T S

PART 1 - GENERAL	1
1.01 SCOPE OF WORK	1
PART 2 - PRODUCTS	1
PART 3 - EXECUTION	1
3.01 STRUCTURE DEMOLITION	1
3.02 PIPING AND EQUIPMENT DEMOLITION.....	1
3.03 SITEWORK DEMOLITION.....	1
3.04 SALVAGE.....	1

**SECTION 02050
DEMOLITION AND SALVAGE**

PART 1 - GENERAL

1.01 SCOPE OF WORK

- A. This section covers the demolition of existing structures, equipment and sitework, and the salvage of existing materials and equipment as set forth herein.
- B. All areas and facilities within the boundaries of the property described in the Notice Inviting Bids are to be demolished as described in Section 3, following. Contractor's work shall not create inconvenience to adjacent property owners, nor shall any adjacent property be disturbed during this contract. Blasting will not be permitted.

PART 2 - PRODUCTS

(NONE THIS SECTION)

PART 3 - EXECUTION

3.01 STRUCTURE DEMOLITION

All structures within the boundaries of District-owned property shall be demolished and the debris shall be removed from the jobsite.

3.02 PIPING AND EQUIPMENT DEMOLITION

All piping and equipment on the user's side of the respective utility purveyor's meters shall be removed and shall become the property of the Contractor. Contractor is responsible to make proper arrangements with each affected utility prior to disconnection.

3.03 SITEWORK DEMOLITION.

Sitework demolition shall include the removal of all concrete, slabs on grade, driveways, sheds, trees and shrubs within the property boundary.

3.04 SALVAGE

- A. All existing materials and equipment shall be removed by the Contractor, shall become the property of the Contractor, and shall be removed from the jobsite.

Demolition and Salvage
Section 02050 – 2

- B. Removal and salvage of any item of equipment or facility shall include removal and salvage of all accessories, piping, wiring, supports and all other appurtenances.

END OF SECTION 02050