

- PROCEDURES FACILITY SIGNAGE GUIDELINES
- 2. EMBOSSED LETTERING SHALL BE CENTERED HORIZONTALLY. LONGER FACILITY NAMES MAY CONTINUE ON A SECOND LINE (4" SPACING BETWEEN) SUBJECT TO DISTRICT REVIEW AND APPROVAL.
- 3. CONTRACTOR TO SUBMIT A COMPLETE WALL ELEVATION AND LETTERING LAYOUT AS A SHOP DRAWING FOR DISTRICT REVIEW AND APPROVAL. DIMENSIONS CONTINGENT UPON DISTRICT APPROVAL OF GENERAL ARRANGEMENT DRAWING INCLUDING FINAL LETTERING LAYOUT.
- 4. THE FONT SHALL BE "COPPERPLATE GOTHIC BOLD", NO EXCEPTIONS.
- 5. REFER TO CONTRACT SPECIAL CONDITIONS FOR ADDITIONAL REQUIREMENTS, IF APPLICABLE.
- 6. REFER TO EMWD'S SPECIFICATIONS FOR MATERIALS REQUIREMENTS AS FOLLOWS:
 - A. SECTION 03150 FORMWORK
 - B. SECTION 03200 REINFORCING


FILE I.D.: \kauai\eng\std dwgs\B-987.dgn

- C. SECTION 03300 CAST-IN-PLACE CONCRETE (FOOTING ONLY)
- D. PRECAST CONCRETE PER PROJECT SPECIFICATIONS
- 7. CONCRETE MIX DESIGN SHALL ACCOUNT FOR CONSTRUCTABILITY ASPECTS RELATED TO THE CONCRETE FINISH AND PLACEMENT OF LETTERS. SUBMIT MIX DESIGN AS A SHOP DRAWING FOR DISTRICT REVIEW AND APPROVAL.
- 8. FRONT AND BOTH ENDS OF WALL SHALL RECEIVE A SHOP-APPLIED ANTI-GRAFFITI COATING SYSTEM PER PROJECT SPECIFICATION, ANTI-GRAFFITI COATING SHALL NOT BE APPLIED TO BACKSIDE OF WALL
- 9. PRIOR TO APPLICATION OF ANTI-GRAFFITI COATING, FRONT AND BOTH ENDS OF WALL SHALL RECEIVE AN ACID WASH FINISH PER EMWD SPECIFICATIONS (UNLESS SCHEDULED OTHERWISE). AND CONCRETE MOISTURE SHALL BE TESTED WITH ELECTRONIC MOISTURE METER.
- 10. OVER-EXCAVATE AND RE-COMPACT SUITABLE MATERIAL TO 90% OF RELATIVE COMPACTION TO A MINIMUM DEPTH OF 12" BELOW THE PROPOSED FOOTING BASE GRADE UNLESS REQUIRED OTHERWISE IN THE FIELD BY THE GEOTECHNICAL ENGINEER.
- 11. CONTRACTOR SHALL COORDINATE LIGHTING LOCATIONS WITH DISTRICT AND INSTALL AS SHOWN ON CIVIL/ELECTRICAL PLANS
- 12. TRENCH BELOW FOOTING FOR LIGHTING CONDUIT SHALL BE FILLED WITH CONCRETE OR 3-SACK SLURRY PER SECTION 16050 BEFORE POURING FOOTING. CONCRETE FILL SHALL BE SAME WIDTH AS FOOTING AND FULL WIDTH OF TRENCH.

MONUMENT SIGN NOTES: /\ /\s\

- (A) FACILITY NAME EMBOSSED LETTERING 6" IN HEIGHT, NAME AND SPELLING PER EMWD.
- DISTRICT NAME EMBOSSED LETTERING 4" IN HEIGHT.
- ADDRESS STREET NUMBER ONLY; TO BE CONFIRMED DURING DESIGN BY LOCAL JURISDICTION. ADDRESS EMBOSSED LETTERING 4" IN HEIGHT. ADJUST HEIGHT BASED ON HEIGHT OF ADJACENT LANDSCAPING
- 8" THICK REINFORCED PRECAST CONCRETE (MIN STRENGTH 4000 PSI) MONUMENT SIGN WALL.
- EMBOSSED LETTERING, DEPTH SHALL BE 1" MIN, 2" MAX.
- 11" WIDE PRECISION PEAKED WALL CAP PRECAST (COPING) BLOCK (ORCO BLOCK COLOR "PORTOLA MW" PRECISION) OR AS SCHEDULED. CONTRACTOR SHALL SUBMIT PHYSICAL SAMPLE FOR DISTRICT REVIEW AND APPROVAL PRIOR TO
- NATURAL CONCRETE COLOR WITHOUT PIGMENT OR STAINS.
- LIGHTING CONDUIT AND GROUND-MOUNTED LIGHTS (SEE **ELECTRICAL DRAWINGS FOR NUMBER FIXTURES AND** SPACING - MIN 2 FIXTURES REQUIRED).
- AFTER WALL FABRICATION, STAIN EMBOSSED LETTERING ON WALL, COLOR: BLACK
- PRECAST WALL LIFTING POINTS. 4T BURKE ERECTION ANCHOR OR APPROVED EQUAL. MINIMUM QUANTITY 4. PRECAST WALL MANUFACTURER TO VERIFY NUMBER OF LIFTING POINTS AND SPACING.

RECOMMENDED



| REVISIONS | | | | | | APPROVALS | | | |
|-------------|---------|---------|---|-------|-------------|--------------|-------------|----------|-------|
| NO. | DATE | INITIAL | DESCRIPTION | APP'D | DATE | | INITIAL | DATE | |
| | | | | | | DESIGN | GK | 11/07/14 | |
| | | | | | | CONSTRUCTION | MI | 11/12/14 | a n |
| 3 | 9/17/21 | ОН | REVISED TO PRECAST WALL, NOTES, DETAILS & TITLE | SVV | 10/6/21 | INSPECTION | CD | 11/10/14 | |
| 2 | 5/3/19 | GS | UPDATED TITLE BLOCK, FONT, AND LOGO | AGA | 5/3/19 | OPERATIONS | | | • • • |
| \triangle | 3/6/15 | GS | REVISED DIMENSIONS AND NOTE C | AGA | 5/15/15 | SUBMITTED | | | |
| REFERENCES: | | | SCALE: NONE | | | | Joe Mouawad | | |
| | | | DDANA(ALD)(GLI | | RECOMMENDED | | Joe 11 | Jouawaa | |

DRAWN BY: OH



11/13/14

DATE

EASTERN MUNICIPAL WATER DISTRICT STANDARD DRAWING

PRECAST FACILITY MONUMENT SIGN

Charlie Bachmann **APPROVED** ASSISTANT GENERAL MANAGER B-987

11/13/14

DATE