



May 17, 2021

**ADDENDUM NO. 2 TO SPECIFICATION NO. 1382W**  
**SAN JACINTO VALLEY RAW WATER CONVEYANCE FACILITIES – PHASE 1 PIPELINE**

This addendum to the specifications is for the purpose of adding, clarifying, or deleting certain information to the construction drawings and project specifications as follows:

**BIDDING SHEETS**

*DELETE* Bid Item No. 10 for Schedule A – Phase 1 Pipeline in its entirety.

**THE BIDDING SHEETS HAVE BEEN UPDATED AND ARE INCLUDED IN THE REVISED PROPOSAL PACKAGED MADE A PART OF THIS ADDENDUM. FAILURE TO SUBMIT THE REVISED PROPOSAL PACKAGE “MAY” DEEM YOUR BID NON-RESPONSIVE**

**SPECIAL CONDITIONS**

**SC-02. Scope of Work**

*REVISE* the second paragraph as follows:

For Schedule A, the work comprises construction of approximately 11,050 linear feet of 60-inch diameter welded steel raw water pipeline, two 30-inch welded steel pipeline bypass connections, a 30-inch above grade suction header connection to the existing Commonwealth Booster Pump Station including buried and non-buried manways, combination air valves, blow off assemblies, cathodic protection, isolation valves, demolition, fencing, trench repair and asphalt concrete grind and overlay, traffic control, hydrostatic testing, pipe connections, all other appurtenances, ~~raising all appurtenances to finished grade,~~ and permitting as shown or specified in the contract documents.

**SC-47. Required Engineering Provisions or Requirements**

*REVISE* the second paragraph as follows:

Esplanade Avenue Widening Project. The City of San Jacinto is planning to widen Esplanade Avenue from Warren Road to Sanderson Avenue. The Esplanade Avenue Widening Project is being coordinated with the District and is expected to begin after construction of this project.

Pipeline appurtenances built along Esplanade Avenue shall be constructed to existing grade with marked locations and protected. ~~Once construction of the Esplanade Avenue Widening Project is completed by the City of San Jacinto (anticipated 18 month construction period), the Contractor shall return within three months of being notified and raise all appurtenances to final grade with the finished improvements to be approved by the District. District may elect to retain or release the Contractor from performing this work upon authorization from District in writing.~~

*ADD the following Special Condition:*

**SC-66. Cathodic Test Station Wire Slack**

For all proposed cathodic test stations within Esplanade Ave between Warren Road and Sanderson Avenue, all wires shall have 4 feet of slack coiled inside the top of the box/station to facilitate potential future raising of grade of the cathodic test stations.

**SECTION P – CONTRACT DRAWINGS**

*DELETE* the following Contract drawings in their entirety and replace with attached. (revisions shown as clouded area)

Drawing No. D-59224

Drawing No. D-59225

Drawing No. D-59226

Drawing No. D-59227

Drawing No. D-59228

Drawing No. D-59229

**EMWD DETAILED PROVISIONS**

**Division 1: General Project Provisions**

*DELETE* 01026 Schedule of Values in its entirety and replace with attached.

**QUESTIONS & ANSWERS**

**J.F. Shea Construction, Inc.**

Q1. On Schedule A Bid Item 10 it is called out as an allowance. However, there is not a budget included. Is this supposed to be an allowance?

A1. DELETE Schedule A Bid Item 10 in its entirety.

- Q2. In Spec Section SC-47 it states to raise appurtenances to grade after future Esplanade widening project with an approximate duration of 18 months. Please provide a date we are to assume this work is to be done. Also please confirm retention will be released when we complete the project, not after to future Esplanade widening project.
- A2. The raising of appurtenances to grade after future Esplanade widening project has been removed from this Project's scope of work in its entirety. Retention will be released when the project is completed.

Eastern Municipal Water District



Joe Mouawad, P.E.  
General Manager

For.

PE: SVV  
PM: [Signature]  
DFE: BAM  
DE: S

JM:SV:sz:ae

ATTACHMENTS: Proposal Package  
Drawing No. D-59224  
Drawing No. D-59225  
Drawing No. D-59226  
Drawing No. D-59227  
Drawing No. D-59228  
Drawing No. D-59229  
01026 Schedule of Values