



August 23, 2019

ADDENDUM No. 2 TO SPECIFICATION NO. 1376W
Well 59 Wellhead Treatment Facility

This addendum to the specifications is for the purpose of adding, clarifying, or deleting certain information to the construction drawings and project specifications as follows:

QUESTIONS & ANSWERS

Stanek Constructors, Inc.

- Q1. On drawing G-02 there is a color schedule, are we recoating the exterior of the perimeter wall with antigraffiti coating per note 2?
- A1. CMU wall recoating is not within the scope of this project. The contractor is instructed in the bid documents to protect the existing wall in-place. Any recoating would only be required on areas of the wall that are affected or damaged by construction.





Schuler Constructors Inc.

- Q1. There is no spec on the cane fiberboard under the tank. Are you able to furnish?
- A1. Cane fiberboard is not required, the contractor shall disregard Note 3 on Drawing D-57757 (Sheet S-03). The backwash tank shall have a concrete floor. The tank shall have a concrete slab foundation as shown in the contract drawings, with the floor of the tank being the top of the concrete slab. The tank floor slopes towards the 8-inch drain at the center of the tank as shown in the contract drawings, and will be designed by the tank manufacturer as described in the structural notes. The connection of the tank wall to the concrete slab or embedded flange shall be part of the manufacturers design. Reference to a floor plate in Detail 2 of Drawing D-57758 (Sheet S-04) shall also be disregarded.

Eastern Municipal Water District



for Joe Mouawad, P.E.
Assistant General Manager,
Planning, Engineering & Construction

PE: 
PM: 
DFE: 
DE: 

DC:ae